


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

00038621

PLUGGING RECORD

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Kern County Land Co. Field _____ Wildcat X
 Lease Name Kritsas Well No. 1 County Rio Blanco
 Location SE of SE Section 8 Township 1N Range 93W Meridian 6 PM
 (Quarter Quarter) 642 feet from S Section line and 906 feet from E Section Line
 N or S E or W

TOTAL DEPTH 7685'DATE OF PLUGGING 9-28-62

DETAILS OF WORK

Plug #1 - 3500' - 3420' W/ 25 sacks Class "A" Cement in 8-3/4" Hole
 Plug #2 - 1935' - 1775' W/ 50 sacks Class "A" Cement in 8-3/4" Hole
 Plug #3 - 1380' - 1300' W/ 25 Sacks Class "A" Cement in 8-3/4" Hole
 Plug #4 - 431' - 363' W/ 25 Sacks Class "A" Cement (Across shoe of 9-5/8" 36# H-40 Surface Casing @398')
 Placed 10 sacks cement at surface and erected abandonment marker.

5/1/63 - A.C. Carroll checked location,
 P&A OK, no marker on hole.

DVR	
WRS	
HHM	
JAM	✓
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date NOV - 1 1962

Director

Company Kern County Land Co. Date 10-24-62407 V&J TowerAddress Midland, TexasPhone No. Mutual 34641

By

D. S. Leetzow
(Signature)Title Dist. Eng.