

PROPOSED HORIZONTAL WELL(S)											
Well Name and Number		Surface Location QQ-Section-Twp-Range			Well Name and Number		Surface Location QQ-Section-Twp-Range		Well Name and Number		Surface Location QQ-Section-Twp-Range
Ardourel 33081718 #2HU		NWSW - 18-33N-8W									
Operator's Wellbore Integrity Contact											
OFFSET WELL EVALUATIONS											
	Offset Well Name	Shortest Horizontal Distance from Offset Well to any Proposed HZ Well	Offset Well Operator	Offset Well Spud Date	Offset Well Status	Offset Well Surface Casing Setting Depth	Depth of Deepest Water Well or Base of Fox Hills (DJ)	Offset Well Top of Production Casing Cement	Most Recent Surface Casing Pressure Reported	Required Comments	
05-067-09201	IGW 112	855	Arkoma Operations, LLC	4/1/2007	PR	570'	320'	0'	1	Shallow Offset. TVD=3272' (FC)	
05-067-09368	IGW 142	815	Arkoma Operations, LLC	7/10/2008	PR	514'	320'	0'	31	Shallow Offset. TVD=3319' (FC)	
05-067-09911	IGW 143	862	Arkoma Operations, LLC	7/22/2014	PR	538'	320'	0'	15	Shallow Offset. TVD=3345' (FC)	
05-067-08185	Julian #1A	870	Arkoma Operations, LLC	2/1/1999	PR	404'	320'	0'	15	Well does not require any mitigation. (DK-SI/MV; TD @8063'); Int Csg @3520' cement	
05-067-07461	Sluggar #1A	1280	McElvain Energy Inc.	3/6/1990	P&A	265'	320'	800'	0	Shallow Offset. TVD=3100' (FC); P&A-3/06/2007: Cement Plugs: 2506'-2744' (24 sxs)	
05-067-09752	Sluggar #22	1319	Advance Wireless Comm	3/9/2010	PR	500'	320'	0'	0	Shallow Offset. TVD=3351' (FC)	
05-067-05412	Helton MV GU #1	1050	Arkoma Operations, LLC	8/5/1958	PR	418'	320'	0'	0	Shallow Offset. TVD=5715' (MV)	
05-067-09317	Sluggar #2	1353	Advance Wireless Comm	3/13/2007	PR	546'	320'	0'	0	Shallow Offset. TVD=3293' (FC)	
05-067-05406	Ignacio 33-8-18	1050	El Paso Natural Gas Co.	7/25/1953	P&A	500'	320'	0'	0	Shallow Offset. TVD=2840' (FC); P&A-6/27/1979: Cement Plugs: 2750'-2900' (57 sxs)	
05-067-09272	IGE 110	635	Arkoma Operations, LLC	5/14/2007	PR	518'	320'	0'	0	Shallow Offset. TVD=3386' (FC)	
05-067-09895	IGE 140	425	Arkoma Operations, LLC	6/4/2013	PR	521'	320'	0'	1	Shallow Offset. TVD= 3573' (FC)	
05-067-08182	Harmon #1A	610	Arkoma Operations, LLC	2/14/1999	PR	456'	320'	0'	0	Well does not require any mitigation. (DK-MV; TD @8135'); Inter Csg @3556' cement	
05-067-08194	Harmon A -1A	920	Arkoma Operations, LLC	3/21/1999	PR	457'	320'	0'	0	Well does not require any mitigation. (DK; TD @8015'). Inter Csg @ 3556' cement	
05-067-09376	Harmon 33-8-17 #2A	923	Red Willow Production Co	8/22/2007	PR	462'	320'	0'	0	Shallow Offset. TVD=3237' (FC)	