

Proposed Wellbore Diagram

**NueVida Resources, LLC
Ardourel 33081718 # 2HU
NWSW Section 18-T33N-R8W
1753' FSL x 295 ' FWL
La Plata County, CO**

API no.: 05-067-xxxxx

GL	6719'
KB	25' (est)

Surface Casing

26" hole @ 500'
20", 94#, K-55HC, LTC @ 500' MD
TOC @ surface w/1366 sxs cmt

Intermediate Casing (1)

17-1/2" hole @ 3,413' MD
13-3/8", 54.5#, J-55, BTC @ 3,413' MD
TOC @ surface w/ 2,592 sxs cmt

Intermediate Casing(2)

12-1/4" hole @ 6,481' MD
9-5/8", 40#, L-80HC, BTC@ 6,481' MD
DV-2 @ 3,313' MD w/ 770 sxs
TOC @ surface
DV-1 @ 5,383' MD w/ 597 sxs
TOC @ 3,313' MD
Stg-1 Cement: 444 sxs, TOC @ 5,383' MD
Total cement: 1811 sxs

$BHL = 17,161' MD$

600' FSL x 479' FEL

$PBHL = 17,040' MD$

600' FSL x 600 ' FEL

Production Casing

8-1/2" hole @ 17,161' MD/6,954' TVD
5-1/2", 20#. P110, BK-HT@ 17,161' MD
TOC @ 2,000' MD
Total cement: 2,899 sxs

