

PROPOSED HORIZONTAL WELL(S)													
Well Name and Number		Surface Location QQ-Section-Twp-Range			Well Name and Number		Surface Location QQ-Section-Twp-Range			Well Name and Number		Surface Location QQ-Section-Twp-Range	
Ardourel 33081718 #5HL		NWSW - 18-33N-8W											
Operator's Wellbore Integrity Contact													
OFFSET WELL EVALUATIONS													
	Offset Well Name	Shortest Horizontal Distance from Offset Well to any Proposed HZ Well	Offset Well Operator	Offset Well Spud Date	Offset Well Status	Offset Well Surface Casing Setting Depth	Depth of Deepest Water Well or Base of Fox Hills (DJ)	Offset Well Top of Production Casing Cement	Most Recent Surface Casing Pressure Reported	Required Comments			
05-067-05427	Julian MV Unit #1	250	Arkoma Operations, LLC	10/10/1959	PR	419'	320'	0'	0	Shallow Offset. TVD=5630' (MV)			
05-067-09751	Julian GU #2	43	Arkoma Operations, LLC	12/24/1992	PR	462'	320'	0'	5	Shallow Offset. TVD=3040' (FC)			
05-067-05749	VD Helton #1	580	Arkoma Operations, LLC	10/18/1951	PR	298'	320'	186'	0	Well does not require any mitigation. (DK: TD @ 7949'); 3stg cement: 6650'-7725' \			
05-067-08175	Helton #1A	610	Arkoma Operations, LLC	11/21/1998	PR	462'	320'	990'	0	Shallow Offset. TVD=5887' (MV). Inter Csg @ 3247, cemented w/ 500 sxs to 990' -C			
05-067-08985	Slugger #1	710	Advanced Wireless, LLC	5/16/2005	PR	320'	320'	0	0	Shallow Offset. TVD= 3290' (FC)			
05-067-09751	Slugger #11	697	Advanced Wireless, LLC	5/5/2010	PR	539'	320'	0'	0	Shallow Offset. TVD=3112' (FC)			
05-067-05426	Harmon #1	910	S.G. Interests I, LLC	4/28/1952	P&A	175'	320'	0'	0	Shallow Offset. TVD=3038' (FC); P&A- 11/14/2002. CIBP @2600'w/2sxs; CICR @ 115			
05-067-09115	Harmon #33-8-17 #1	710	Red Willow Production Co	5/17/2006	PR	362'	320'	0'	0	Shallow Offset. TVD= 3315' (FC)			
05-067-09901	IGE 141	686	Arkoma Operations, LLC	5/27/2014	PR	512'	320'	0'	0	Shallow Offset. TVD= 3590' (FC)			
05-067-05439	Harmon MV Unit #1	910	Arkoma Operations, LLC	9/27/1958	PR	414'	320'	0'	0	Shallow Offset. TVD= 5635' (MV)			
05-067-07930	Harmon GU #A-2	700	Arkoma Operations, LLC	12/17/1992	PR	450'	320'	0'	0	Shallow Offset. TVD=-3090' (FC)			
05-067-09023	IGE 401	685	Elm Ridge Expl Co, LLC	6/28/2006	P&A	541'	320'	0'	0	Well does not require any mitigation.(DK: TD@8195'). P&A- 11/03/2014 . Cemen			
05-067-09365	Harmon 33-8-17 #3	80	Red Willow Production Co	8/15/2007	PR	443'	320'	0'	0	Shallow Offset. TVD=3320' (FC)			
05-067-05418	Harmon DK-MV GU #1	118	Arkoma Operations, LLC	8/5/1958	P&A	443'	320'	3365'	0	Well does not require any mitigation.(DK: TD@8017'). P&A-1/16/2013. Cement P			