

Location Name: Tinker 2 05-007-06176

Location ID 378705



Rerouted the water to drain properly



Utilized rock to slow water down.

Location Name: Tinker 2 05-007-06176

Location ID 378705



Filled in erosion



Water bars installed

Location Name: Tinker 2 05-007-06176

Location ID 378705



Seeded access road with Pinyon Juniper seed mix

Table 10-1. Prescribed Pinyon/Juniper Woodlands-Sagebrush Community Seed Mix.

Common Name	Scientific Name	Variety	Season	Form	PLS lbs/acre ¹
Fourwing saltbush	<i>Atriplex canescens</i>	VNS	Cool	Shrub	2.0
Winterfat	<i>Krascheninnikovia lanata</i>	VNS	Cool	Shrub	2.0
Sand dropseed	<i>Sporobolus cryptandrus</i>	VNS	Warm	Bunch	0.5
Galleta	<i>Pleuraphis jamesii</i>	Viva florets	Warm	Bunch/Sod-forming	3.0
Indian ricegrass	<i>Achnatherum hymenoides</i>	Paloma or Rimrock	Cool	Bunch	4.0
Bottle brush squirreltail	<i>Elymus elymoides</i>	Tusas or VNS	Cool	Bunch	3.0
Blue flax	<i>Linum lewisii</i>	Apar	Cool	Forb	0.25
Rocky Mtn. bee plant	<i>Cleome serrulate</i>	Local collection or VNS	Cool	Forb	0.25
Artemesia ²	<i>Artemesia</i>	VNS	Cool	Shrub	0.25

¹Based on 60 PLS per square foot, drill seeded; double this rate (120 PLS per square foot) if broadcast or hydro-seeded.

² *Wyomingensis* or *nova* depending on site.