

US Treatment Report



Customer: CIVITAS RESOURCES
Rep: Josh Klieson
Supervisor: VITALIJS NEVERDASOV

Rig: Patterson 572
Well: Bijou 3-65-21-22-23 2BH

Job #: JOB00192421
Job Date: 9/1/2024
Time Requested: 17:30

Job Type: US Primary
 Casing-Surface

UWI: Bijou 3-65-21-22-23 2BH
Surface: Bijou 3-65-21-22-23 2BH

Time Arrived: 15:00
Time Released: 23:55

1447.4 sk MAG S 13.3 + 0.10% MCDF-P

Yield: 1.44 ft³/sk = 371.21bbls Mix Water: 7.01 gal/sk = 10146.27gal

BHCT (F)	105	BHST (F)	144	Casing Size (in)	9.625
Casing Grade	J-55	Casing Weight (lb/ft)	36	Casing Size (in)	9.625
Casing Grade	J-55	Casing Weight (lb/ft)	36	Float Depth (ft)	3481
Funnel Vis (sec/qt)	TBD	Max Pressure (psi)	1500	Mud Density (lb/gal)	8.5
Mud Type	WATER	Plug Size (in)	9 5/8	Plug Type	Rig
TMD (ft)	3530	TVD (ft)	3250		Supplied

CASING SET @ 3520'.

Treatment Info: Sacks Used: 1447 Sacks Not Used: 0

Preflush: 10bbls Fresh Water & 10bbls MAG Mark & 10bbls Fresh Water

				Circulation Time:	0.5		
				Slurry Temp:	85	Bulk Sample:	Yes
				Water Temp:	78	Water Sample:	Yes
				Bulk Temp:	70	Slurry Sample:	Yes
				Air Temp:	78	Air Pressure	
Slurry Returns:	58	Plug Bumped:	Yes	Pump Out Lines:	Yes	Float Held:	Yes
Cement Class:			OWG	Humidity:	25	Precipitation:	

Displace: 269.1 BBLS FRESH WATER

Further Blend Details:

Prehydrated: NO

Additional Details (General Notes): TD 3530.

CASING SET @ 3520. FLOAT COLLAR
 3481'.

Time	Pressure psi	Annular Pressure psi	Volume Per Stage bbls	Total Stage Volume bbls	Rate bbls/mi n	Treatment Detail
15:00	0.00					Arrive on Location - ARRIVED ON LOCATION. CUSTOMER REQUESTER CREW @ 17:30.
15:30	0.00					TEST WATER: TEMP 78/ CHLORIDES 110/ PH 8.0
19:21	0.00					Safety Meeting - PRE JOB SAFETY MEETING
20:36	3,140.00		5.0		4.0	Start Pressure Test - LOAD LINE AND PRESSURE TEST
20:39	380.00		10		4.0	Pump Preflush - PUMP FRESH WATER
20:41	490.00		10		4.0	Pump Preflush - PUMP DYE
20:43	370.00		10		4.0	Pump Preflush - PUMP FRESH WATER

20:45	620.00		371.2		6.3	Pump Slurry - BATCH/ WEIGHT/ PUMP 1447.4 SKS OF MAG S 13.3 PPG.
21:49	0.00					Stop Pumping - FINISHED PUMPING CEMENT
21:50	0.00					Drop Plug - DROP TOP PLUG
21:52	1,250.00		260		7.0	Displace - FRESH WATER DISPLACEMENT. FIRST 20 BBLS WASHING UP ON TIO OF THE PLUG.
22:38	1,120.00		9.1		4.0	Slow Rate Pumping - SLOW RATE
22:40	1,513.00			269.1		Bump Plug - BUMP PLUG. 58 BBLS OF CEMENT TO SURFACE.
22:41	0.00					Check Floats - FLOATS HELD. 1 BBL BACK
22:50	0.00					Rig Out
23:00	0.00					Wash Up Truck



Customer: CIVITAS

Date: SEPT 1 2024

Ticket: 192421

Location: BIJOU 3-65-21-22-23 2BH

Well Name: BIJOU 3-65-21-22-23 2BH

Job Type: SURFACE

Magnum Unit #: 1015

