



DAILY DRILLING REPORT

SCANNED

RECEIVED

AUG 22 1978

COLO. OIL & GAS CONS. COM.

NAME OF WELL: KISSINGER ET AL - FORD #6-8
LOCATION: SE/4 NW/4 SECTION 8-T 34S-R 44W, BACA COUNTY, COLORADO
OPERATOR: KISSINGER PETROLEUM CORPORATION
CONTRACTOR: SNYDER DRILLING COMPANY
ELEVATIONS: GL 4120' KB 4130' TD 5200' MORROW TEST
NORTHFLANK PROSPECT

5-23-78 131', WOC. Spudded 6 PM 5-22-78. Drld 17-1/2" hole to 131'. Ran and cem 3 jts (106.02') 48# 13-3/8" csg at 116' KB w/150 sx Type "H", 3% CaCl₂. Plug down 4 AM 5-23-78. Good cement returns. Mud: 9.2, Visc 34

5-24-78 420', Drilling, Dev: 1/4° at 420'. Mud: 9.1, Visc 32

5-25-78 1480', Drilling, Mud: 9.3, Visc 34, LCM 6#/bbl

5-26-78 1610', Drilling, Drld 420' 12-1/4" hole. Ran and cem 10 jts (406') 24# 8-5/8" casing at 416' KB w/325 sx Type "H", 3% CaCl₂. Plug down 3:20 PM 5-25-78. Dev: 0° at 1580'. Mud: 9, Visc 30, LCM 2#/bbl

5-27-78 2300', Drilling, Mud: 9.4, Visc 32, LCM 6#/bbl

5-28-78 2715', Tripping for bit #3, Dev: 1/2° at 2345'. Mud: 9.2, Visc 29, LCM 1#/bbl

5-29-78 3065', Drilling, Dev: 1/4° at 2795'. Mud: 9.2, Visc 31, LCM 3#/bbl

5-30-78 3440', Drilling, Mud: 9.2, Visc 31, LCM 4#/bbl

5-31-78 3725', Drilling, Mud: 9.3, Visc 32, LCM 3#/bbl

6-1-78 3980', Drilling, Mud: 9.2, Visc 36, WL 15, LCM 3#/bbl

6-2-78 4200', Drilling, Mud: 9, Visc 37, WL 14.8, LCM 3#/bbl

6-3-78 4340', Drilling, Dev: 1/4° at 4287', Mud: 9.0, Visc 40, WL 15, LCM 4#/bbl

6-4-78 4580', Drilling, Mud: 9, Visc 39, WL 13, LCM 4#/bbl

6-5-78 4780', Drilling, Mud: 9, Visc 44, WL 11, LCM 2#/bbl



RECEIVED

DAILY DRILLING REPORT

SCANNED

AUG 22 1978

COLG. OIL & GAS CONS. COMM.

NAME OF WELL: KISSINGER ET AL - FORD #6-8
LOCATION: SE/4 NW/4 SECTION 8-T 34S-R 44W, BACA COUNTY, COLORADO
OPERATOR: KISSINGER PETROLEUM CORPORATION
CONTRACTOR: SNYDER DRILLING COMPANY
ELEVATIONS: GL 4120' KB 4130' TD 5200' MORROW TEST
NORTHFLANK PROSPECT

-2-

- 6-6-78 4950', Waiting on mechanic, trouble with pump motor, Mud: 8.8, Visc 38, WL 10.5, LCM 3#/bbl
- 6-7-78 5125', Drilling. Mud: 8.9, Visc 44, WL 10.2, LCM 3#/bbl
- 6-8-78 5225', Drilling, Mud: 8.9, Visc 44, WL 10, LCM 10#/bbl
- 6-9-78 5415', Drilling, Mud: 9.0, Visc 47, WL 9.2, LCM 12#/bbl
- 6-10-78 Touched TD
- 6-11-78 Logging
- 6-12-78 TD 5475', WELL PLUGGED AND ABANDONED, Ran logs as follows: IES and Density-GR.
LOG TOPS:
- | | | | |
|----------|--------------|-------------|--------------|
| Red Cave | 1862 (+2268) | Morrow | 5029 (- 899) |
| Topeka | 3180 (+ 950) | Keyes | 5312 (-1182) |
| Lansing | 3558 (+ 572) | Miss. | 5447 (-1317) |
| Marmaton | 4088 (+ 42) | Drillers TD | 5470 (-1340) |
| Cherokee | 4344 (- 214) | Loggers TD | 5475 (-1345) |
| Atoka | 4715 (- 585) | | |
- 6-13-78 TD 5475'. WELL PLUGGED AND ABANDONED.
Plugged well as follows: 30 sx Base of Sfc
10 sx Top of Sfc
Plug down 12 noon 6-11-78. Rig released 12 noon 6-11-78.
FINAL REPORT.