

OPERATOR: K.P. Kauffman Company Inc.
WELL: UPRR 43 PAN AM I #26
FIELD: SPINDLE
API # 05-123-09095
LEASE #: _____
UIC #: _____

CNTY: DACONO/WELD
STATE: CO
SPUD: 1/8/1977
COMP: 4/14/1977
STATUS: PA
WBD DATE: 3/13/2025

FTG: _____
Q-Q: NESW
SEC.: 13
TWS: 1N
RGE: 68W
BY: _____

PROPOSED P&A WELLBORE DIAGRAM

Set 10 Sx Cmt @ Surf

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>754</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4962</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4824</u>	<u>4850</u>	<u>54</u>		

TOC @ 615 '

Pump 66 Sx Cmt
Perf @ 804 '

Fox Hills Bottom: 665'
Deepest Water Well in 1 mi: 620'

TOC @ 3902 '

Set 8 Sx Cmt @ 4002 '

2 Sx Cmt on Top
Set CIBP @ 4774 '

SUSSEX Perfs
4824'-4850'