

Well Name:	UPRR 15-7
Location:	660' FSL, 1980' FEL, SWSE Sec 7, T3S, R65W
County:	Adams
API #:	05-001-08350
Co-ordinates:	39.800022 / -104.703985
Elevations:	GROUND: 5421'
	KB: --
Depths (KB):	PBTD: --
	TD: 8524'

<b>Surface Casing:</b>	
Drilled 12-1/4" surface hole to 302'	
Set 9-5/8", 36# casing at 302'	
Cemented with 300 sks	
TOC at surface	
<b>Production Casing:</b>	
None	
<b>Open Hole:</b>	
Assumed 7-7/8" Open Hole from 302'-8,524', expected to be washed out	
<b>Tubing:</b>	
None	
<b>Rods:</b>	
None	
<b>Perforations:</b>	
None	
<b>P&amp;A Plugs:</b>	
1. 10 sks from 25' to surface	
2. 35 sks from 279'-350'	
3. 120 sks from 1450'-1850'	
<b>Additional Notes:</b>	
<b>Initial Potential Test:</b>	
<b>Formation Tops:</b>	
Denver	211'
Upper Arapahoe (Base)	888'
Lower Arapahoe (Base)	1184'
Fox Hills	1500'
Fox Hills (Base)	1804'
Niobrara	7650'
D Sand	8383'
J Sand	8418'

## Proposed Wellbore Schematic

Well Name: UPRR 15-7  
 Location: 660' FSL, 1980' FEL, SWSE Sec 7, T3S, R65W  
 County: Adams  
 API #: 05-001-08350  
 Co-ordinates: 39.800022 / -104.703985  
 Elevations: GROUND: 5421'  
 KB: --  
 Depths (KB): PBTD: --  
 TD: 8524'

Date Prepared: 10/2/2024  
 Last Updated: 3/14/2025  
 Spud Date: 12/5/1983  
 Completion Start Date: 12/14/1983  
 Last Workover Date: 12/14/1983  
 Prepared by: Jake Van Bramer  
 Updated by: --

