

**State of Colorado
Energy & Carbon Management Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203

Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

404144269

Receive Date:

Report taken by:

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by ECMC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

OPERATOR INFORMATION

Name of Operator: NOBLE ENERGY INC	Operator No: 100322	Phone Numbers
Address: 1099 18TH STREET SUITE 1500		Phone: (970) 313-5582
City: DENVER	State: CO	Zip: 80202
Contact Person: Jason Davidson	Email: jason.davidson@chevron.com	Mobile: ()

PROJECT, PURPOSE & SITE INFORMATION**PROJECT INFORMATION**

Remediation Project #: 31082 Initial Form 27 Document #: 403498455

PURPOSE INFORMATION

- ☐ Rule 913.c.(1): Pit or Cuttings Trench closure.
- ☐ Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- ☐ Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- ☐ Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- ☐ Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- ☐ Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- ☐ Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- ☐ Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- ☒ Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- ☐ Rule 913.g: Changes of Operator.
- ☐ Rule 915.b: Request to leave elevated inorganics in situ.
- ☐ Other: _____

SITE INFORMATION

No Multiple Facilities

Facility Type: WELL	Facility ID: _____	API #: 123-16321	County Name: WELD
Facility Name: HUNTSMAN G 13-9	Latitude: 40.310550	Longitude: -104.604642	
** correct Lat/Long if needed: Latitude: _____		Longitude: _____	
QtrQtr: NESE	Sec: 13	Twp: 4N	Range: 65W
Meridian: 6	Sensitive Area? Yes		

SITE CONDITIONS

General soil type - USCS Classifications SW Most Sensitive Adjacent Land Use Grassland

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? No

Other Potential Receptors within 1/4 mile

Freshwater Emergent Wetland 0.2mi NE
No other potential receptors are located within ¼ mile of the Site.
Above distances are approximations.

SITE INVESTIGATION PLAN

TYPE OF WASTE:

☒ E&P Waste ☐ Other E&P Waste ☐ Non-E&P Waste

☒ Produced Water ☐ Workover Fluids

☒ Oil ☐ Tank Bottoms

☒ Condensate ☐ Pigging Waste

☐ Drilling Fluids ☐ Rig Wash

☐ Drill Cuttings ☐ Spent Filters

☐ Pit Bottoms

☐ Other (as described by EPA)

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
UNDETERMINED	GROUNDWATER	NA	Lab analysis if encountered
No	SOILS	NA	Lab analysis

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

Pursuant to ECMC Rule 911 a site investigation will be conducted pertaining to the HUNTSMAN G 13-9 wellhead cut and cap and flowline removal. Approximately 1183' of flowline will be removed, however a portion of the flowline will be abandoned-in-place due to field constraints. The ECMC will be updated in a supplemental Form 27. The wellhead will be cut and capped per ECMC rules. Additionally, soil samples will be field screened at the N-E-S-W sides of the wellhead. Soil samples will be taken along the flowline any points of material change and/or hammer unions, directional changes, as well as at the bell holes on either side of a waterway. The Flowline Pre-Abandonment Notice Document number is included under Related Forms.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

A grab soil sample will be collected at the base of the excavation or the area showing the highest degree of impact during field screening activities at the wellhead excavation. Additionally, soil samples will be field screened at the N-E-S-W sides of the wellhead. Soil samples will be taken along the flowline at any points of material change and/or hammer unions, directional changes, as well as at the bell holes on either side of a waterway. Soil samples will be analyzed by a certified laboratory for the full extent of Table 915-1, including but not limited to: TPH (total volatile [C6-C10] and extractable [C10-C36] hydrocarbons) organic compounds in soil per ECMC Table 915-1, and EC, SAR, pH, metals, and boron. All samples collected will be analyzed by a certified laboratory using approved ECMC laboratory analysis methods.

Proposed Groundwater Sampling

☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

If groundwater is encountered during the site investigation a grab groundwater will be collected and analyzed for all organic compounds per ECMC Table 915-1.

Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

Visual inspection of the wellhead and flowline areas will occur during abandonment activities. Field personnel will field screen all disturbed areas using visual and olfactory senses to determine if laboratory confirmation sampling is required. The ECMC Flowline Closure and Wellhead Closure Checklists will be utilized and filled out during the abandonment process. A photolog will be submitted on the Subsequent Form 27.

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 4
Number of soil samples exceeding 915-1 1
Was the areal and vertical extent of soil contamination delineated? Yes
Approximate areal extent (square feet) 100

NA / ND

ND Highest concentration of TPH (mg/kg) _____
-- Highest concentration of SAR 2.54
BTEX > 915-1 No
Vertical Extent > 915-1 (in feet) 6

Groundwater

Number of groundwater samples collected 0
Was extent of groundwater contaminated delineated? Yes
Depth to groundwater (below ground surface, in feet) _____
Number of groundwater monitoring wells installed _____
Number of groundwater samples exceeding 915-1 _____

_____ Highest concentration of Benzene (µg/l) _____
_____ Highest concentration of Toluene (µg/l) _____
_____ Highest concentration of Ethylbenzene (µg/l) _____
_____ Highest concentration of Xylene (µg/l) _____
_____ Highest concentration of Methane (mg/l) _____

Surface Water

0 Number of surface water samples collected
_____ Number of surface water samples exceeding 915-1
If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☒ Were background samples collected as part of this site investigation?

Sixteen background soil samples were collected from an area not impacted by oil and gas development and at similar depths and lithologies as confirmation soil samples collected at the location and analyzed for Table 915-1 metals and soil suitability for reclamation standards (pH, EC, SAR, and Boron). Background soil sample analytical results were reported with elevated levels of pH, EC, SAR, arsenic (As), barium (Ba), cadmium (Ca) and lead (Pb).

Background Soil Sample Analysis (mg/kg)

pH @ 0.5': Max = 8.68
pH @ 4': Max = 9.52
pH @ 5': Max = 9.11
EC @ 0.5': Max = 0.748
EC @ 4': Max = 5.36
EC @ 5': Max = 4.10
SAR @ 0.5' & 4': Max = <6.00
SAR @ 5': Max = 9.61
As @ 0.5': Max*1.25 = 4.10
As @ 4': Max*1.25 = 10.2
As @ 5': Max*1.25 = 6.54
Ba @ 0.5': Max*1.25 = 119
Ba @ 4': Max*1.25 = 296
Ba @ 5': Max*1.25 = 248
Ca @ 0.5': Max*1.25 = 0.415
Ca @ 4': Max*1.25 = 0.613
Ca @ 5': Max*1.25 = 0.458
Pb @ 0.5': Max*1.25 = 13.6
Pb @ 4': Max*1.25 = 15.5
Pb @ 5': Max*1.25 = 14.8

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) _____ Volume of liquid waste (barrels) _____

☒ Is further site investigation required?

Background samples will be collected in five locations from an area not impacted by oil and gas development at similar depths (7' and 8') and lithologies as confirmation samples collected at the location and analyzed for ECMC Table 915-1 metals and soil suitability for reclamation standards (SSR) (pH, EC, SAR, and Boron). The samples will be used to characterize native soil and potentially attribute elevated metals and inorganics concentrations to native soil conditions.

Elevated inorganics and metals were observed in one discrete location at the former HUNTSMAN G 13-9 wellhead. Soil will be resampled and analyzed for the full Table 915-1 analyte suite at the WH-FS-01@6' sample location at the same depth where the initial elevated concentrations were observed. Additional background samples will be collected to characterize native soil conditions. Noble will request an NFA be granted if the reanalyzed samples comply with the Table 915-1 concentration standard. Refer to the attached proposed site investigation plan for sample locations.

Alternatively, if the sample results exceed the Table 915-1 standards and cannot be attributed to native soil conditions via background soil characterization a minimum of five additional samples will be collected to delineate the magnitude and extent of elevated constituents.

Following completion of the delineation, Noble will submit a detailed reclamation plan to address elevated SSR constituents that includes, but is not limited to, soil analysis from adjacent undisturbed lands, revegetation techniques, site stabilization, and details of seeded species and will request NFA designation be granted under Rule 915.b: Request to leave elevated inorganics in situ.

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Impacted soil was not discovered during the wellhead cut and cap activities or during removal of the flowlines. Based on site investigation activities and laboratory analytical results of confirmation soil samples collected from the wellhead excavation floors and flowline risers, along the flowlines, and from the separator flowline riser, removal of soil is not needed. The material excavated during cut and cap and flowline removal activities was used as backfill for the excavations.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Based on site investigation activities and laboratory analytical results for confirmation soil samples collected from the wellhead excavation floors and flowline risers, along the flowlines, and from the separator flowline riser, a remediation plan is not needed.

Soil Remediation Summary

☐

In Situ

☐

Ex Situ

Bioremediation (or enhanced bioremediation)

Excavate and offsite disposal

Chemical oxidation

If Yes: Estimated Volume (Cubic Yards)

Air sparge / Soil vapor extraction

Name of Licensed Disposal Facility or ECMC Facility ID #

Natural Attenuation

Excavate and onsite remediation

Other

Land Treatment

Bioremediation (or enhanced bioremediation)

Chemical oxidation

Other

Groundwater Remediation Summary

Bioremediation (or enhanced bioremediation)

Chemical oxidation

Air sparge / Soil vapor extraction

Natural Attenuation

Other

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

If groundwater is encountered during additional site assessment activities, a grab groundwater sample will be collected and analyzed for all organic compounds and inorganic parameters per Table 915-1.

REMEDATION PROGRESS UPDATE

PERIODIC REPORTING

Approved Reporting Schedule:

☒ Quarterly☐ Semi-Annually☐ Annually☐ Other

☐ Request Alternative Reporting Schedule:

☐ Semi-Annually☐ Annually☐ Other

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

Report Type:

☐ Groundwater Monitoring☐ Land Treatment Progress Report☐ O&M Report☒

Other Timeline Update and Supplemental Site Investigation Proposal

Adequacy of Operator's General Liability Insurance and Financial Assurance

Describe the adequacy of the Operator's general liability insurance and Financial Assurance to fully address the anticipated costs of Remediation, including the estimated remaining cost for this project (below).

If this information has been provided on a Form 27 within the last 12 months, provide the Document Number of that form.

Noble intends to directly address the costs of remediation at the locations as part of our asset retirement obligation process and operations. Noble has general liability insurance (policy MWZZ 316714) and financial assurance in compliance with ECMC rules. Records are available on the ECMC's website. The cost for remediation is an estimate only, costs may change upwards or downward based on site-specific information. Noble makes no representation or guarantees as to the accuracy of the estimate.

Operator anticipates the remaining cost for this project to be: \$ 50000

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? No

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

Volume of E&P Waste (solid) in cubic yards

E&P waste (solid) description

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility:

Volume of E&P Waste (liquid) in barrels

E&P waste (liquid) description

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility:

REMEDATION COMPLETION REPORT

REMEDATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No

If YES:

☐

Compliant with Rule 913.h.(1).

☐

Compliant with Rule 913.h.(2).

☐

Compliant with Rule 913.h.(3).

Do all soils meet Table 915-1 standards? Yes

Does the previous reply indicate consideration of background concentrations? Yes

Does Groundwater meet Table 915-1 standards? Yes

Is additional groundwater monitoring to be conducted? _____

Operator shall comply with the ECMC 1000-Series Reclamation Requirements for all impacted and disturbed areas.

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Reclamation will be in accordance with ECMC 1000 Series Rules.

Is the described reclamation complete? Yes

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☒ Interim ☐ Final

Did the Surface Owner provide the seed mix? _____

If YES, does the seed mix comply with local soil conservation district recommendations? _____

Did the local soil conservation district provide the seed mix? _____

SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. 10/31/2025

Proposed date of completion of Reclamation. 10/31/2027

IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 08/10/2023

Actual Spill or Release date, or date of discovery. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 11/17/2023

Proposed site investigation commencement. 09/15/2023

Proposed completion of site investigation. 11/30/2025

REMEDIAL ACTION DATES

Proposed start date of Remediation. _____

Proposed date of completion of Remediation. _____

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

☒ Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

The implementation schedule has been changed due to the necessity for supplemental site investigation activities adjacent to the former HUNTSMAN G 13-9 wellhead. The proposed site investigation will be completed following the approval of this form.

OPERATOR COMMENT

In response to ECMC Form 27 Comment dated 1/8/2025 (Document Number 403900705): This SF27 represents a 1Q25 TU for the Huntsman G 13-9 WH and flowline abandonment activities conducted in November 2023 and January 2024. The WH sampling was conducted by Eagle Environmental Consulting in November 2023 and identified no organic or inorganic exceedances. A secured analytical data report is attached and data summarized in the attached Eagle data package. In January 2024, Fremont Environmental conducted sampling activities along the flowline. Upon receipt of a secured laboratory report, analytical findings will be summarized and provided.

The Operator will conduct a additional site investigation collecting resamples at WH-FS-01@6' to confirm the presence or absence of the elevated inorganic and metals concentration. Additional background samples will also be collected to characterize native soil conditions. Please refer to the site investigation as outlined in this proposed Site Investigation Report workplan and the attached proposed Site Investigation Plan for sample locations. The Operator will complete the additional site investigation activities as outlined in the proposed Site Investigation Report workplan following the approval of this form.

Quarterly reporting will be conducted until closure criteria are achieved for the remediation project. The results of the supplemental site investigation will be submitted on a subsequent Form 27.

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Ethan Black

Title: Consultant

Submit Date: _____

Email: ethanb@fremontenv.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with ECMC Rules and applicable orders and is hereby approved.

ECMC Approved: _____

Date: _____

Remediation Project Number: 31082

COA Type**Description**

0 COA	

ATTACHMENT LIST

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num**Name**

404144274	SITE INVESTIGATION PLAN
404144275	SITE INVESTIGATION REPORT
404144276	ANALYTICAL RESULTS

Total Attach: 3 Files

General Comments**User Group****Comment****Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)