




OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO



PLUGGING RECORD

075-06847

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator British-American Oil Producing Company Field Wildcat XX
Lease Name Dickenson Well No. 1 County Logan
Location NW, SW, Section 10 Township 10 N Range 53 W Meridian 6PM
1980 feet from South Section line and 660 feet from West Section Line
N or S E or W

TOTAL DEPTH 5165'KB DATE OF PLUGGING 6-11-57

DETAILS OF WORK

Filled hole with heavy mud from bottom to 5045, spotted 50 sax cement plug from 5045 to 4844, heavy mud from 4844 to 60, 10 sax cement plug in bottom of surface casing, heavy mud from top of plug to 15', 5 sax cement plug in top of surface casing, erected marker, filled cellar with soil, levelled and abandoned location.

Table with 2 columns and 8 rows: AJJ, DVR, FJK, WRS, HHA, AH, JJD, FILE



I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: Date JUN 18 1957 Company British-American Date 6-12-57
Address Box 180, Denver 1, Col Phone No. AC 2 9401
Director A. J. Gersin By [Signature] Title Dist Supt

T