

# COLORADO OIL AND GAS CONSERVATION COMMISSION SUNDRY NOTICES AND REPORTS OF WELLS

OIL & GAS  
CONSERVATION COMMISSION

(Indicate nature of data by checking below)



OIL & GAS  
CONSERVATION COMMISSION

Notice of intention to drill (attach plat) ☒ X  
 Notice of intention to change plans \_\_\_\_\_  
 Notice of date for test of water shut-off \_\_\_\_\_  
 Report on result of test of water shut-off \_\_\_\_\_  
 Notice of intention to re-drill or repair well \_\_\_\_\_  
 Notice of intention to clean out well \_\_\_\_\_  
 Statement of shooting \_\_\_\_\_  
 Statement of perforating \_\_\_\_\_  
 Notice to pull or otherwise alter casing \_\_\_\_\_  
 Notice of intention to abandon well \_\_\_\_\_  
 Report of work done on well since previous report \_\_\_\_\_

Locate Well Correctly

		14	X

Notice to do work ☒ X  
 Report of work done ☐

Land: Fee and Patented ☒ X  
 State ☐

Lease No. W/C

Colorado State Eagle County Posey Creek Prospect Field  
Frank Benton Land and Livestock Co. SE SE NE 14 3S 85W 6th P.M.  
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 2333 Ft. (N) of Section Line and 354 Ft. (E) of Section Line.  
 (S) (W)

The elevation above sea level is 10,100 Ft. (estimated)

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

It is proposed to drill an exploratory test for oil or gas to approximately 7450 feet. Tentative casing program is:

16" Conductor pipe at approximately 50 feet, cemented to surface.  
 10-3/4" O.D. 40.5# surface casing to approximately 800 feet, cemented to surface.  
 7" 23# and 26# oil string casing to deepest potentially productive oil or gas sand, cemented with sufficient cement to shut off any potentially productive zones up the hole.

## Objective Zones:

Morrison 480'  
 Entrada 530'  
 Schoolhouse 1560'  
 Minturn 4700'  
 Belden 6250'  
 Leadville 6850'

AJJ	
DVR	
FJK	
CPS	
BHM	
AH	
JJD	✓
FILE	

Approved: MAY 25 1955

Date May 20, 1955

Company The California Company

Address Box 780, Denver, Colorado

By E. H. Pickett

Title Division Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.