

OIL AND GAS CONSERVATION COMMISSION

DEPARTMENT OF NATURAL RESOURCES

STATE OF COLORADO



00405452

for Patented and Federal lands.
for State lands.

RECEIVED

NOV 21 1980

COLD OIL & GAS CONS. COMM.

5. LEASE DESIGNATION AND SERIAL NO.

FEE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

- - -

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

UPRR Amoco

9. WELL NO.

#7-6

10. FIELD AND POOL, OR WILDCAT

Wildcat

11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

Sec. 7, T3S, R64W

12. COUNTY

Adams

13. STATE

Colorado

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1.

OIL WELL ☐ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR

Sohio Petroleum Co.

3. ADDRESS OF OPERATOR

P.O. Box 30, Casper, WY 82602

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)

At surface SE NW (1980' FNL & 1980' FWL)

At proposed prod. zone Same

14. PERMIT NO.

801026

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

GL 5442' KB 5452'

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐

(Other) 3 Zone Test

PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON ☐CHANGE PLANS ☐

X

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT ☐(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work _____

1. Perforate "J" Sand 8122-38 & test. Acidize w/1000 gal 7 $\frac{1}{2}$ % acid & test.
2. If non commercial, set CIBP @ + 8110 & dump 1 sx cmt on plug.
3. Perforate "D" Sand 8046-76 & test. Acidize w/1500 gal 7 $\frac{1}{2}$ % Hcl acid & test.
4. If non-commercial, set CIBP @ +7750 & dump 1 sx cmt on plug.
5. Perforate Timpas 7648-58 & test. Acidize w/1000 gal 28% Hcl & test & frac if necessary.
6. If zones test non-commercial, well will be plugged & abandoned per O&G Commission instructions. If a zone tests commercial, completion will be made at that point. Pending results of bond logs, block cement squeezes may be performed over test intervals detailed above.

18. I hereby certify that the foregoing is true and correct

SIGNED

D.R. Holcomb

TITLE Asst. Dist. Supt.

DATE 11-19-80

(This space for Federal or State office use)

APPROVED BY

M. Rogers

TITLE

DIRECTOR
O&G CONS. COMM.

DATE

NOV 24 1980

CONDITIONS OF APPROVAL, IF ANY: