

001-07655



GAS CONSERVATION COMMISSION
DEPARTMENT OF NATURAL RESOURCES
THE STATE OF COLORADO

Application for Patented and Federal lands.
 Application for State lands.

RECEIVED

JAN 23 1981

COLO. OIL & GAS CONSERV. COMM.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
 Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER Dry Hole		5. LEASE DESIGNATION AND SERIAL NO. Fee	
2. NAME OF OPERATOR Sohio Petroleum Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME ---	
3. ADDRESS OF OPERATOR P. O. Box 30, Casper, Wyoming 82602		7. UNIT AGREEMENT NAME ---	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface C SE NW At proposed prod. zone Same		8. FARM OR LEASE NAME UPRR Amoco	
14. PERMIT NO. 801026		9. WELL NO. 7-6	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 5442' GR; 5450' KB		10. FIELD AND POOL, OR WILDCAT Wildcat	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 7, T3S, R64W	
		12. COUNTY Adams	13. STATE Colorado

16. **Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data**

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETION ☐ABANDON ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT ☒

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. **DESCRIBE PROPOSED OR COMPLETED OPERATIONS** (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work December 22, 23 & 26, 1980

- Spot sand on bottom to cover perfs from 8046'-76'. Tag sand plug at 8040'.
- Spot 2 sx of cement on sand from 8040'-8012' with dump bailer.
- Circulate hole with 9.0 ppg gel.
- Cut 4½" casing at 6754' and pull out of hole.
- Went in hole with tubing to 6800'. Spotted a 20 sx cement plug in and out of 4½" csg.
- Picked up to 1750' and spotted a 100 sx cement plug over the Fox Hills.
- Picked up to 280' and spotted a 50 sx cement plug 50' in and out of surface casing. POH.
- Spotted a 10 sx cement plug at the surface.



18. I hereby certify that the foregoing is true and correct

SIGNED

W. H. Ward

TITLE District Superintendent

DATE 1-20-81

(This space for Federal or State office use)

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DIRECTOR
GAS CONSERV. COMM.

DATE JAN 26 1981



00405446